

PACKET A STORMWATER PERMIT

Howard County & City of Kokomo, Indiana

Erosion and Sediment Control for Individual Lots Within a Permitted Project

The following are required:

- 1.) A '**Declaration of Responsibility**' shall be submitted
- 2.) Comply with the provisions and regulations developed by the Permitted Project.
- 3.) Installation and maintenance of a stable construction access.
- 4.) Installation and maintenance of appropriate perimeter erosion and sediment control measures prior to land disturbance.
- 5.) Sediment and discharge and tracking from each lot must be minimized throughout the land disturbing activities on the lot until permanent stabilization has been achieved.
- 6.) Clean-up of sediment that is either tracked or washed onto roads.
 - a. Bulk clearing of sediments shall not include flushing the area with water.
 - b. Cleared sediment must be redistributed or disposed of in a manner that is in compliance with all applicable statutes and regulations.
- 7.) Adjacent lots disturbed by an individual lot operator must be repaired and stabilized with temporary or permanent surface stabilization.
- 8.) Unvegetated areas that are scheduled or likely to be left inactive for fifteen (15) days or more must be temporarily or permanently stabilized with measures appropriate for the season to minimize the erosion potential. Vegetated areas with a density of less than seventy percent (70%) shall be restabilized using appropriate methods to minimize the erosion potential.
- 9.) Final stabilization meeting the criteria in Rule 5 is achieved when the individual lot operator:
 - a. Completes final stabilization.
 - b. Has installed appropriate erosion and sediment control measures for an individual lot prior to occupation of the home by the homeowner and has informed the homeowner of the requirement, and benefits of, final stabilization.